

KJG BUILDING

Keith Greaves
07980 456 855

INVOICE

Customer: Dunchurch Council

Date: 12th Oct '18

Labor cost:

£550.00

Description of jobs being carried out:

Re-newing of timber on 3 park benches.
} 1 park bench on the square - (Dun 16)
} 1 park bench on Rugby Road - (Dun 45)
} 1 park bench on Coventry Road - (Dun 34)

Price of materials:

Materials required; Hard wood £380.00
Bolts + fixings £41.50

* Hire of generator for power tools £100.00

Total price of materials:

Total price £521.50

Skip required

Yes/No
 No

I, the customer, agree to the work above to be carried out on materials. I will pay the above labor charge upon completion of job.

(Date) I will supply and pay for the above.

IF PAYING BY CHEQUE. PLEASE MAKE PAYABLE TO MR K GREAVES

(Signature)

Please note: Any further materials that may be required, there will be an extra charge for. Any hard removable materials left over from jobs undertaken, I will remove unless the customer states that they require them. I cannot remove old materials from site unless they are of a size I can dispose of by hand at local tip.

The £521.50 for materials I will need upfront
So I can order materials.

Total Price of job overall £1071.50

Estimate

1 December 2018

Tel: 01788 - 84099

Lindsey Foster
Dunchurch Parish Council
Dunchurch Community Library
School Street
Dunchurch CV22 6PA**Benches****Estimate for supplying and fitting the replacement of missing timbers only, to three benches:-****Rugby rd. (the heath)**

Fit new 'seating' rail, bolted to steel frame.

(1) rail 3"x2", @ 70¾".

Daventry rd. (the square)

Fit a 'back rest'; bolted to the concrete frames.

Fix battens to support rails.

(2) battens 2"x2", @ 16" at either end of bench.

Fit (6) rails 1¾"x¾", @ 94¼" fixed to the battens at either end.

Coventry rd.

Secure a rail to the 'back rest', fixed to concrete frames (at either end of bench).

(1) rail 3"x 2", @ 72".

NB: All new replacement wood to be treated with 'Osmo' oil; 'I would suggest cedar colour'.
All new replacement wood 'Sapele'.
Sapele is a uniform durable hardwood, suitable for external joinery and would be easy to maintain.

Materials and Labour**£ 693.00**

I suggest a second estimate could be considered in the spring of 2019, or as soon as the weather would permit sanding down the existing wood. All though some of the original wood may not be suitable for restoring and some pieces may also need replacing; I suggest waiting until the weather improves, to see if it is possible to save a lot of the original timber. Using various types of electric powered sanders in warm dry weather, then treating with 'Osmo' oil to match in with any new timber would be more economical. The two benches on 'the Green' could also be considered in the spring of 2019.

Yours faithfully



S. Wilkinson